

Contract No	ESC2024-043				
Description	Construction of Concrete Footpath at the Georgetown Independent Living Facilit				
Tenderer					
Please Note: Cells shaded in green must be completed, all other cells are locked for editing					
Item	Description of Work	Est Qty	Unit	Rate (\$) (GST Ex)	Amount (\$) (GST Ex)
A	Construction of Concrete Footpath at the Georgetown Independent Living Facilit				\$ -
TOTAL CONTRACT AMOUNT					\$ -
<p><i>This schedule is NOT a Bill of Quantities but it may be used during the contract period to supplement other forms of assessing the value of the Works completed for payment purposes.</i></p> <p><i>The Tenderer hereby acknowledges and agrees that the Principal does not guarantee or warrant the accuracy or completeness of the information provided in this Schedule and declares that the Tenderer has not relied on this information in the preparation of its Tender.</i></p> <p><i>The Tenderer further acknowledges and agrees that the Tenderer is responsible for taking out its own quantities and determining the actual quantities of the work required. The Tenderer hereby releases the Principal now and forever any liability whatsoever as a result of or arising from the supply of this information.</i></p>					
Item No	Description of Work	Est Qty	Unit	Rate (\$) (GST Ex)	Amount (\$) (GST Ex)
	All works are to be performed in accordance with Etheridge Shire council Specification for Road and Drainage Construction and ESC Standard Drawings, unless otherwise specified. All works priced in this bill of quantities must be inclusive of business overheads, profit, site establishment, management of quality assurance systems, traffic control, environmental management and oh&s management.				
	SITE PREPARATION				
	Site Establishment, Site Management, Set Out of Works, & Protection of Works				
1.	Site establishment and setting out of the Works as specified	1	Item		
2.	Site establishment and setting out of the works as specified. Inclusive of; Job Site Analysis and pre-commencement survey (including any repegging if required), Locating all underground services (if required) in and near the site prior to commencement of works and reporting to Superintendent on any critical service locations should discrepancies between proposed works. Site establishment including construction of site access, Supply, erection and hire of site sheds/containers for construction period duration, Project Signs, Survey, set out and monitoring of the works by a licensed surveyor, Other preliminaries including supervision, insurances, etc.	1	Item		
	Excavation works				
3	Excavation and dispose of unsuitable material as directed.	243	m ³		
	Crushed dust				
4	Supply, spread and compact 50 mm thick crushed dust	54	m ³		
	Reinforcement concrete				
5	Supply, lay and compact 25Mpa concrete with SL 72 mesh and required formworks including other accessories	636	m ²		
6	Supply, lay and compact 25Mpa concrete with SL 72 double mesh and required formworks including other accessories	338	m ²		
	Concrete work for lay back				
7	Supply, lay, compact of 32Mpa concrete for Layback	6	No		
	Concrete work for of Kerb Ramp				
8	Construction of kerb ramp per S1016D, with N25 concrete, SL72 mesh, 1:8 slope, smooth transitions, and non-slip finish.	7	No		
	Supply and laying of PVC Sheets				
9	Supply and installation of PVC sheets, including material delivery, surface preparation, cutting, laying, and securing, complete as per specifications and drawings	731	m		
	REINSTATEMENT WORKS				
10	Final clean up, removal of all temporary structures and reinstatement to all disturbed areas to equal or better than pre-existing conditions. Disturbed nature strip to be sown and fertilised with Council approved grass seed mixture.	1	Item		
	WAE Drawings				
11	Preparation of WAE drawing s	1	Item		
12	All works and obligations in the contract but not included elsewhere in this schedule of lump sum prices. (if not detail and break down of the sum entered given, the amount will be deducted from the lump sum)	1	Item		
TOTAL LUMP SUM AMOUNT for ITEM A					